

3CP 1 – MOBILIZATION**PART 1 GENERAL****1.01 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General Conditions and Special Provisions, and other Technical Specification Sections apply to this Section.

1.02 SUMMARY

- A. This Section specifies contractor is responsible for all preparatory work and operations required prior to beginning work.

1.03 GENERAL

- A. Mobilization shall include, but not limited to, the following:
 - 1. Movement of personnel, tools, equipment, materials, supplies, and incidentals to the project site and all preparatory work.
 - 2. Establishment of all necessary facilities for the Contractor's convenience
 - 3. Obtaining permits necessary for the execution of the work and adhere to conditions of existing permits.
 - a. USACOE 404, CDFW Streambed Alteration Agreement, and RWQCB 401 certification have been obtained for this project
 - b. Revise existing or acquire a new EBRPD Encroachment Permit as required to cover work period and Contractor.
 - 4. Providing required bonds and proof of insurance.
 - 5. Upon completion of the work, Contractor shall remove tools, equipment, and unused materials and supplies from the Project site and restore all disturbed areas outside the Project area to their pre-construction condition.
- B. Owner has the right to reject construction tools, equipment, materials, and supplies which are, in Owner's opinion, unsafe, improper, or inadequate.
 - 1. Contractor shall bring rejected construction tools, equipment, materials, and supplies to an acceptable condition as approved by Owner or remove from the Project site.

1.04 SUBMITTALS

- A. Projected Work Schedule: The Contractor will provide a Work Schedule acceptable to Owner or its representative, to be discussed at the pre-construction meeting, fixing the dates at which the various phases of work will be performed. The Contractor's work schedule shall not supersede any working days period stated in the Agreement. No payment will be made by Owner to the Contractor until the Work Schedule has been received and approved by the Owner's representative/Resident Project Manager. Failure to make Work Schedule and/or request and receive approval of appropriate adjustments will cause Owner to delay payments to Contractor.
- B. Detour Plan: Contractor shall provide a Marsh Creek Trail detour plan if Contractor anticipates trail closures during construction. Trail closures will not be permitted without an approved trail detour plan.

1. Contractor shall install informational, closure and detour signs routing users. All signs shall meet mutcd standards. Signs shall be posted on marsh creek trail 30 days prior to construction informing public about trail closures and detours resulting from this project. Maintain public access to and along The Marsh Creek Regional Trail to the greatest extent feasible.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.01 PROGRESS OBSERVATIONS

- A. A written notice or phone call requesting site observation shall be given to the O.R. at least (1) one week prior to any anticipated observation date.
- B. The following progress observations are required:
 1. Observation of all on-site mock-ups prior to installation.
 2. Observation and approval of subgrade for all installations noted in this Specification, prior to installation.